

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 50 N.R. 6W


Chippewa COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 21 and 28.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 8-14-63 with R. Norkali, D.F.

WITNESSES TO CORNER..... 8" Jack Pine (¼ S. N.B.T.) S. 20° W., 13½ lks.



7" Jack Pine (¼ S. N.B.T.) S. 50° E., 32 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from one Red Pine B.T. bearing N. 51° W., 10 lks. a stump with Face and scribe marks "B.T." and a W. Pine stump bearing S. 40° E., 04 lks. with a face, Notch and overgrowth. Record Notes indicate the latter distance to be 40 links.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 4/27/64  
REGISTERED LAND SURVEYOR