

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Chippewa COUNTY
T 50N R 6W

DESCRIPTION OF CORNER Sec. Cor. for Sections 33-34, on the Township Line

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 7-14-71

WITNESSES TO CORNER..... 9" Jack Pine (S33 NBT) N40°W 26.9'



9" Jack Pine (S34 NBT) N86°E 31.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by Single Proportionate measure along the township line, between $\frac{1}{4}$ Corner, $\frac{1}{2}$ mile West and a closing corner 1 mile East. Found no original evidence at corner but did find a recorded line tree to West and an old blazed Jack Pine to East.

Corner lies in a low, wet marsh.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE

9-28-71

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68