

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co. One Corner

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> N. S. , R. <u>6</u> E. W.	G-2A
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-4, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-2A Witness Corner to Meander Corner bet. Sec's 3-4, on shore of Lake Superior.

Meander Corner set by Wells Burt, D.S. in 1849.

Bearings were:

W. Birch 7", S20 $\frac{1}{2}$ ^oW, 205 lks. and W. Birch 5", S48^oE, 227 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-2A Placed Witness Corner on an extension of a line of original corners 2.3 miles South. Shore line has eroded considerable. Witness corner lies 247.1' South of record location for the meander corner. Corner lies 85' South of a high sandbank and 90' North of a trail.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


G-2A Set 1" pipe with 4" aluminium cap at Witness Corner.

Bearings are: 16" W. Pine, N34^oW, 29.2', and 16" W. Pine, S37^oW, 35.2' and 14" R. Pine, S75^oE, 10.4'

NOTE: See sketch on reverse side.

SIGNED BY Billy D. Buckler
Billy D. Buckler

DATE 8-25-75



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____