

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

1 Corner

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 50 N. 8. R. 6 W.	C-12
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. , RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gerald L. Wiggins, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-23, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C-12 East 1/4 Corner of Section 31. D.N.R. L.S. Billy D. Buckler placed a 1" pipe with aluminium cap at this corner on 6-25-79. Bearings were: 8" J. Pine, S36⁰E, 28.3'
7" J. Pine, N54⁰E, 23.9'
8" J. Pine, N03⁰W, 41.1'

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-12 Buckler replaced corner from a bearing tree, NW of corner. Scribe marks were plain. Buckler's 1979 bearing trees have been cut. Marked new witt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Re-Witt. D.N.R. Monument.

C-12 8" W. Pine, N8⁰W, 87.5'
8" W. Pine, N54⁰W, 51.8'
12" R. Pine, N86⁰W, 83.1'
6" Oak, S47⁰W, 90.0'

SIGNED BY Gerald L. Wiggins
Gerald L. Wiggins
SURVEYOR'S MICHIGAN REGISTRATION NO. 23521

DATE 9-20-84

