

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Chippewa Co.

One Corner.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> ^{N.} / _{K.} R. <u>6</u> ^{K.} / _{W.}	<u>A-2</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ ^{N.} / _{S.} R. _____ ^{E.} / _{W.}	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} / _{S.} R. _____ ^{E.} / _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-6, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-2 Quarter Corner on Westside of Section 6, was set by Austin Burt D.S. in 1840.
Bearings were: Spruce 7", S53°W, 23 lks. and Spruce 5", N75°W, 47 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-2 Placed $\frac{1}{4}$ Corner on an extension of a line North on the westside of Section 7. Found no evidence of original witnesses. Corner lies on margin of timber growth, bordering Lake Superior. Waters edge is 110' North of $\frac{1}{4}$ corner. Original Meander corner is recorded as being 14.55 chains (960.3') North of the $\frac{1}{4}$ corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 Placed 1" pipe with 4" aluminum cap at the corner.

New Bearings: 10" Jack Pine, N48°W, 14.6' and 14" Jack Pine, S20°W, 94.6' and 14" W. Pine, S28°E, 55.2'

NOTE: See sketch on reverse side.

SIGNED BY Billy D. Buckler DATE 8-25-75



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____