

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

1 Corner

| FOR CORNERS OF--                           | LOCATED IN--  | CORNER CODE NUMBER |
|--|---|--------------------|
| 1. PUBLIC LAND SURVEY _____                | T. <u>50</u> N. <u>X</u> R. <u>6</u> W.                 | <u>I-11</u>        |
| 2. PROPERTY CONTROLLING IN SECTION _____   | , T. _____ N. _____ S. _____ R. _____ E. _____ W. _____ | _____              |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | , T. _____ N. _____ S. _____ R. _____ E. _____ W. _____ | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____      |   |                    |
| 5. PRIVATE CLAIMS _____                    |   |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-1, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

**I-11 Sec. Cor. 26-27-34-35, set by this department on 11-13-69.**

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

**I-11 Raised corner to near road surface. Found former monument, 3.0' deep. One former witness; 10" Cedar, S7°W, 31.0' is missing. 2" Iron Pipe, East, 120.2' also missing.**

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**I-11 Placed 1" pipe with 4" aluminium cap on top of old monument.**

1969 witness; 12" W. Pine, N26°W, 36.6'.

New Bearings: 14" W. Pine, S26°W, 122.9' & 6" Cedar, S19°E, 78.2'.

Corner is buried in center of road to West and in line with West edge of Road to South.

SIGNED BY Billy D. Buckler DATE 8-21-80

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_