

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>6W</u>	<u>E11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 11 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E11) Corner common to Sections 28-29-32-33. 1979 - Billy D. Buckler RLS remonumented the corner at record bearing and distance from the two original BTs, Cedar 6" S29W 13 links and Cedar 6" N62E 11 links, both found in good condition. Set 1"ID I.pipe with 4" aluminum cap. 14" W.Pine N70E 44.1', 8" Cedar S14E 22.0', 10" Cedar N58W 21.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E11) Found the 1979 monument in good condition and at record bearing and distance from the 1979 NBTs, all in good condition with open blazes, and at record bearing and distance from the original Cedar BTs, both alive and green. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E11) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 11" Cedar S12E 22.2' old marks *
 11" Cedar N57W 22.35' do *
 17" W.Pine N74E 45.1' do *
 7" Cedar S52W 12.7' mrkd "S32 NBT"
 Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1979 NBT



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/28/07

For the Michigan Department of Natural Resources, Office of Land and Facilities

