

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>6W</u>	<u>E12</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Jun 11 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E12) Quarter corner common to Sections 32 and 33. 1979 - Billy D. Buckler RLS remonumented the corner in the original position as determined from two original witnesses, stumps in proper position, also a R.Pine scribed "G.J.W. 1941". Set 1" pipe with 4" aluminum cap. 8" R.Pine N15E 19.2', 14" R.Pine N38W 26.35', 6" J.Pine S41W 19.65'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E12) Recovered the 1979 monument in good condition and at record bearing and distance from the 1979 witnesses. The Red Pine witnesses are in good condition. The J.Pine is dead. Also recovered the original BTs Y.Pine N62W 45 links and Y.Pine S55E 22 links, now both stumps with notches visible, at record bearing and distance. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E12) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 17" R.Pine N34W 26.85' open blazes *
 13" R.Pine N18E 19.6' mrkd "1/4S" *
 11" J.Pine S30E 12.7' "1/4S NBT"
 11" J.Pine S79W 37.95' do
 Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1979 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/28/07

