

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>6W</u>	<u>E13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

Jun 18 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20 ____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E13) Standard Section corner common to Sections 32 and 33. 1969 - Billy D. Buckler RLS remonumented the corner at record bearing and distance from an original BT Jack Pine N54W 43 links. Set 1" pipe with 4" aluminum cap. 7" J.Pine North 34.3', 9" J.Pine N74E 22.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E13) Recovered the 1969 monument in good condition and at record bearing and distance from the 1969 witnesses, both in good condition with open blazes and marks visible. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E13) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 9" J.Pine N05E 34.75' open blazes *
 11" J.Pine N77E 23.2' do *
 13" R.Pine S10E 44.97' mkrd "S4 NBT"
 7" R.Pine S12W 47.93' do
 Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1969 NBT



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/28/07

For the Michigan Department of Natural Resources, Office of Land and Facilities

