

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>6W</u>	<u>F11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 11 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F11) Quarter corner common to Sections 28 and 33. 1979 - Billy D. Buckler RLS remonumented the corner at record bearing and distance from the stumps of the original bearing trees, W.Pine S71E 77 links, and Y.Pine N52W 75 links. Set 1"ID I.pipe with 4" aluminum cap. 10" R.Pine S42W 26.6', 10" R.Pine S57E 42.3', 8" R.Pine N71E 22.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F11) Found the 1979 monument at record bearing and distance from the stump remains of the NW 0BT Y.Pine N52W 75 links, notch visible, and from the 1979 NBT R.Pine N71E 22.1'. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F11) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 13" R.Pine S61W 26.3' mrkd "1/4S" *
 14" R.Pine S39E 42.65' do *
 12" R.Pine N75E 22.5' do *
 11" R.Pine N27W 27.55' mrkd "1/4S NBT"
 Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1979 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/28/07

For the Michigan Department of Natural Resources, Office of Land and Facilities

