

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>6W</u>	<u>F13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

*T50N-R6W*

Jun 11 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(F13) Standard Quarter corner on the south side of Section 33. 1969 - Billy D. Buckler RLS remonumented the corner in the original position as determined from two original W.Pine BTs, N04E 12 links, and N62W 19 links. Set 1" pipe with 4" aluminum cap. 16" R.Pine N43W 24.6', 12" R.Pine N36E 6.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F13) Found the 1969 monument in good condition and at record bearing and distance from the 1969 witnesses and from the remains of the two W.Pine OBTs noted in the 1969 record. The lower face and notch are visible on the W.Pine N04E. The W.Pine N62W is a rotted stump. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F13) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:  
 14" R.Pine N43E 6.8' mrkd "1/4S" \*  
 19" R.Pine N41W 25.25' do \*  
 8" R.Pine S42W 11.4' mrkd "1/4S NBT"  
 8" twin Oak S15E 17.7' do  
 Bearings are magnetic. Distances are to nail with MDNR tag. \* denotes 1969 NBT.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/28/07

For the Michigan Department of Natural Resources, Office of Land and Facilities