

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Chippewa

(County)

Located In:

Corner Code #

- |                                       |                          |            |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey                 | T <u>50N</u> R <u>6W</u> | <u>G11</u> |
|                                       | T _____ R _____          | _____      |
|                                       | T _____ R _____          | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                          |            |
| 5. Private Claims                     |                          |            |

Jun 05 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(G11) Corner common to Sections 27-28-33-34. 1963 - Billy D. Buckler, RLS remonumented the corner in the original position as determined from a W.Pine OBT stump S42E 24 links, and R.Pine line trees 6.07 ch. east and 2.40 ch. north. Set 1" pipe with 4" brass cap. 14" R.Pine S89E 44 links, 15" W.Pine S80W 57 links, 12" R.Pine N02E 60 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G11) Recovered the 1963 monument in good condition and at record bearing and distance from the 1963 witnesses, all recovered in good condition with overgrown blazes. The W.Pine OBT stump noted in the 1963 record was not recovered. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G11) Found 1" ID I.pipe with 4" alum.  
 MDNR cap. Set measuring nails in:  
 17" R.Pine S83E 29.58 \*  
 22" W.Pine S86W 38.18 mrkd "S33" \*  
 17" R.Pine N07E 39.3' "S27" \*  
 8" B.Spruce S36W 18.57' "S33 NBT"  
 Bearings are magnetic. Distances are to nail with MDNR tag. \* denotes 1963 NBT.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	27	28	27	26	25								
11													
12	31	32	33	34	35	36							
13													



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/28/07