

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>6W</u>	<u>G13</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Jun 12 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(G13) Standard Section corner common to Sections 33 and 34. 1971 - Billy D. Buckler RLS reestablished the corner by single proportionate measurement along the township line between 1/4 corner 1/2 mile west and closing corner 1 mile east. Set 1" pipe with 4" aluminum cap. 9" J.Pine N40W 26.9', 9" J.Pine N86E 31.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G13) Recovered the 1971 monument in good condition and at record bearing and distance from the 1971 NBTs, now both stumps. Checked the position of the monument with respect to the corners noted on the 1971 record and found it to be 0.21' East and 3.41' North of the position described in record. Accepted the monument as a careful and faithful reestablishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G13) Found 1" ID I. pipe with 4" alum. MDNR cap. Set measuring nails in:  
 5" W.Pine S89W 7.0'      mrkd "S3 NBT"  
 5" J.Pine S48E 17.9'      do  
 4" J.Pine S27E 16.35'      do  
 5" Spruce N41E 7.47'      "S34 NBT"  
 Bearings are magnetic. Distances are to nail with MDNR tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/28/07

For the Michigan Department of Natural Resources, Office of Land and Facilities