

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S 33 T 50N R 6W	2
	S 33 T 50N R 6W	14
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11							●					
12	31	32	33	34	35	36						
13							●					

Jun 11 2007

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(2-Sec. 33) East 1/16 corner between Sections 28 and 33. Established in 1981 by Eino Sainio, midway and on line between Section and Quarter corners 1325.1' east and west. Set 18" capped T-iron. 5" J.Pine N65W 26', 5" J.Pine S14W 16'.
 (14-Sec. 33) South 1/16 between Sections 33 and 34. 1979 - Billy D. Buckler RLS perpetuated the position established by Corey Hughes RLS 20706, midway and on line between Quarter corner to north and Section corner to south. Set 1" ID I.pipe with 4" aluminum cap. 6" J.Pine N07E 22.1', 7" J.Pine S34W 6.3', 9" J.Pine S81E 31.85'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(2-Sec. 33) Found and accepted the 1981 monument, a T-iron with cap stamped "Sainio 7873" at substantially the record position and at record bearing and distance from the 1981 witnesses, both in good condition with overgrown blazes. Left the monument in place and made new witnesses.
 (14-Sec. 33) Found and accepted the 1979 monument in good condition and at the record position: substantially midway and on line between adjacent Section and Quarter corners. The 1979 BTs were not recovered. Left the monument in place and made new witnesses. The corner lies 15' west of a NE/SW trail.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Found T-iron with cap "Sainio 7873"	(14) Found 1" ID I.pipe with 4" alum.
Set measuring nails in:	MDNR cap. Set measuring nails in:
8" J.Pine S17W 16.35' mrkd "E1/16" *	6" W.Pine N80E 68.43' mrkd "S1/16 BT"
8" J.Pine N62W 26.05' do *	8" R.Pine N58E 113.82' do
8" J.Pine N03E 20.1' mrkd "E1/16 BT"	13" W.Pine S38W 121.07' do
6" J.Pine N70E 21.0' do	7" Spruce N86W 63.43' do
Bearings are magnetic. Distances are to nail with MDNR tag. * denotes 1981 BT.	Bearings are magnetic. Distances are to nail with MDNR tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/28/07

For the Michigan Department of Natural Resources, Office of Land and Facilities