

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___ R ___	_____
2. Property Controlling in Section	S 33 T 50N R 6W	7
	S 33 T 50N R 6W	6
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jun 05 2007

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- (7-Sec. 33) North 1/16 between Sections 33 and 34. Not established in the original survey.
- (6-Sec. 33) Northeast 1/16 corner, Section 33. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (7-Sec. 33) Established the corner midway and on the section line between Section corner 1322.03' north and Quarter corner 1322.03' south. The position for the corner falls in the east side of a N-S trail road. From the position thus established, I found a 3/4" iron pin, placed by persons unknown, S64E 5.15' distant, which I did not accept as marking the position for the corner.
- (6-Sec. 33) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |   |
|---|---|
| (7) Set 1"IDx36" I.pipe w/ plastic cap stamped "MICH DNR PS33986" below the surface of a N-S trail. Set measuring nails in: | (6) Set 1"IDx36" I.pipe w/plastic cap stamped "MICH DNR PS33986". Set measuring nails in: |
| 10" J.Pine S30E 9.1 mrkd "N1/16 BT"   | 10" J.Pine S08W 9.8' mrkd "NE1/16 BT"   |
| 5" J.Pine N46E 15.25' do  | 6" W.Birch N77E 57.36' do   |
| 10" J.Pine N23W 21.3' do  | 10" J.Pine S39W 31.4' do  |
| 8" J.Pine N82W 48.6' do   | 6" J.Pine N25W 23.2' do   |
| Bearings are magnetic. Distances are to nail with MDNR tag.   | Bearings are magnetic. Distances are to nail with MDNR tag.                               |



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/28/07