

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>50N</u> R <u>6W</u>	<u>18</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 07/09/2007 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Quarter corner common to Sections 22 and 23. 1849 - Established by Wells Burt, Deputy Surveyor. Set post. Pine 18" S31E 52 links, Pine 28" N29W 58 links. 1958 - Remonumented by Billy D. Buckler RLS: Replaced 1/4 corner from two pine B.T.s bearing S70W 56 links with face and notch remaining, stump bottom bearing NW 48 links. Set 1" pipe with 4" brass cap. 6" Jackpine S74E 23 links, 8" Jackpine S47W 54 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the 1958 monument in good condition and at record bearing and distance from the 1958 NBTs. The Jackpine SE is in good condition. The Jackpine SW has been windthrown. I note that the original BTs given in the 1958 record are those for the original 1849 Meander Corner between Sections 23 and 26, not the 1/4 corner I8. I suspect that the Meander Corner BTs were transcribed to the 1958 record in error. The Michigan Dept. of Natural Resources, on whose behalf Mr. Buckler monumented this corner, does not have a copy of Mr. Buckler's original field notes, but only a notation which appears to have been made after the fact, in the office. I record this corner under the presumption that Mr. Buckler properly reestablished the corner from the recovered remains of the original bearing trees given in the original record for the 1/4 corner and accept the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 11" J.Pine S72E 15.27' old blazes (1958 NBT)
 5" R.Pine S21W 7.86' mrkd "1/4S NBT"
 8" R.Pine S82W 44.77' do
 R.Pine N37E 47.0' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 01/26/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities