

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co. Four Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S., R. _____ E. W.		10-Sec.12 11-Sec.12 12-Sec.12 11A-Sec.12
2. PROPERTY CONTROLLING IN SECTION <u>12</u> T. <u>50</u> N. S., R. <u>7</u> E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on 9-21 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
10-Sec.12 South 1/16 Cor. bet. Sec's. 11 and 12.

11-Sec.12 South West 1/16 Cor. Sec. 12

12-Sec.12 South 1/16 Cor. Sec. 12

11-A-Sec.12 Meander Corner, on West 1/16 line, on South shore of Betsy River.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
10-Sec.12 Corner placed midway bet. Sec. Cor. to South and $\frac{1}{4}$ Cor. to North.

11-Sec.12 Corner placed at intersection of lines, quartering the Southwest quarter Section.

12-Sec.12 Corner placed midway bet. Center of Section and the South quarter cor.

11A-Sec.12 Corner placed, on West 1/16 line, 1,037.0' North of S.W. 1/16 Corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" Brass or Aluminium cap at all corners.

10-Sec.12 Bearings: 12" R. Pine, S74°W, 27.0' and 8" Jack Pine, N7°W, 16.2'

11-Sec.12 Bearings: 8" J. Pine, N10°W, 16.1' and 12" J. Pine, N78°E, 16.1'


12-Sec.12 Bearings: 6" J. Pine, N25°W, 5.0' and 6" J. Pine, S23°W, 24.3'

11A-Sec.12 Bearings: 7" J. Pine, S18°E, 2.4' and 10" J. Pine, S89°W, 12.6'

SIGNED BY Billy D. Buckler

DATE 10-16-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____