

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

Three Corners.

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 50 N. R. 2 E.	L-5, K-5, K-4
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 9-21-1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
All Corners set by Wells Burt, D.S. in 1849.

- L-5 $\frac{1}{4}$ Corner bet. Secs. 12-13
Bearings were: S. Pine 10", N71°E, 15 lks. and S. Pine 10", S26°W, 21 lks.
- K-5 Sec. Cor. 11-12-13-14.
Bearings were: S. Pine 10", S86°W, 41 lks. and S. Pine 8", N25°E, 39 lks.
- K-4 $\frac{1}{4}$ Cor. bet. Secs. 11-12.
Bearings were: S. Pine 12", S34°W, 17 lks. and S. Pine 6", N23°E, 23 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corners:

- L-5 Corner re-established, midway and on line bet. two Sec. Cora.
- K-5 Corner replaced from one original B.T. in poor condition, N25°E, 39 lks.
- K-4 Found a squared Oak Tree with dead Pine stump, S20°W, 5.0'. Stump scribed "S. NBT" but not an original. Used corner as marked by another Land Surveyor.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" Brass or Aluminium cap at all corners.

- L-5 New Bearings: 7" Jack Pine, S4°W, 18.3' and 10" Jack Pine, N84°E, 19.0'
- K-5 New Bearings: 7" Jack Pine, N12°E, 7.5' and 9" Jack Pine, S58°W, 23.2'
- K-4 New Bearings: 8" Red Pine, S86°W, 12.0' and 10" Red Pine, S50°E, 22.6'

SIGNED BY Billy D. Buckler
Billy D. Buckler

DATE 10-2-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____
CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____