

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

Three Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 50 N. R. 2 E. W.	K-3, L-3, L-4
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on 9-21 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
All Corners set by wells Burt, D.S. in 1849.

- K-3 Sec. Cor. 1-2-11-12
Bearings were: S. Pine 6", S66°E, 40 lks. and S. Pine 7", N35°W, 25 lks.
- L-3 ¼ Cor. bet. Secs. 1-12
Bearings were: S. Pine 10", N16°E, 24 lks. and S. Pine 8", S21°W, 59 lks.
- L-4 Center of Sec. 12.
This corner was not set during the original survey.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-3 Found old post, a squared J. pine and a dead stub, scribed (S. NBT) bearing N50°E, 12.0'. Lines marked about 50 Years ago.
- L-3 Replaced corner from remains of both witnesses
- L-4 Corner placed at intersection of quarter lines as required for proper Section Sub-division.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" cap at all corners.

- K-3 New Bearings: 12" Jack Pine, S62°E, 58.8' and 6" Jack Pine, S48°W, 40.6'
- L-3 New Bearings: 9" Red Pine, S47°W, 42.6' and 7" Jack Pine, S33°E, 1.9'
- L-4 New Bearings: 6" Jack Pine, S75°W, 11.4' and 8" Jack Pine, S26°E, 11.5'

SIGNED BY Billy D. Buckler Billy D. Buckler DATE 10-2-73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____