

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Chippewa Co.

One Corner.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> N. <u>X</u> , R. <u>7</u> W. <u>X</u>	I-12
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 9-11, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

I-12 Quarter Corner bet. Sec's. 34-35, set by Wells Burt, D.S. in 1849.
Bearings were: W. Pine 10", S36°E, 32 lks. and Fir 8", N40°W, 13 lks.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

I-12 Corner replaced from one W. Pine bearing tree; a stub in poor condition, with calloused overgrowth showing out line of the face, notch and scribe marks. Found wood post bottom in proper position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-12 Placed 1" pipe with 4" aluminium cap at corner.
New Bearings: 7" Jack Pine, S52°W, 72.2' and 8" Jack Pine, South, 54.9'
Corner lies in an open clearing.

SIGNED BY Billy D. Buckler *Billy D. Buckler* DATE 8-25-75



SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____