

Chippewa Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Chippewa Co. 3 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. _____ N. _____ S., R. _____ E. _____	7-Sec.10
2. PROPERTY CONTROLL- ING IN SECTION	T. 50 N. _____ S., R. 7 E. _____	8-Sec.10 9-Sec.10
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ S., R. _____ E. _____	
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 8-6, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
7-Sec.10 North 1/16 Corner on East side of Section 10.

8-Sec.10 West 1/16 Corner of Section 10.

9-Sec.10 East 1/16 Corner of Section 10.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

7-Sec.10 Placed corner midway bet. Sec. Cor. to North and $\frac{1}{4}$ Cor. to South.

8-Sec.10 Placed corner midway bet $\frac{1}{4}$ Cor. to West and Center Cor. to East.

9-Sec.10 Placed corner midway bet. $\frac{1}{4}$ Cor. to East and Center Cor. to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" aluminium cap at all corners.


7-Sec.10 Bearings: 18" W. Pine, N73°E, 18.8' and 26" W. Pine, S71°E, 21.0' and
6" W. Pine, S40°W, 17.0'.

8-Sec.10 Bearings: 16" Hemlock, N57°E, 15.9' and 8" Hemlock, N23°W, 10.1' and
12" Y. Birch, S34°W, 26.4'.

9-Sec.10 Bearings: 8" W. Pine, N26°E, 44.0' and 10" J. Pine, S86°W, 36.0' and
10" J. Pine, S31°E, 18.2'.

SIGNED BY Billy D. Buckler
Billy D. Buckler
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

DATE 9-10-79



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____