

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T___ R___

T___ R___

T___ R___

T___ R___

2. Property Controlling
in Section

S_14 T_50N R_7W

S___ T___ R___

3. Miscellaneous

S___ T___ R___

Property in Sec.

S___ T___ R___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Oct 28 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5									●				
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
(1-Sec. 14). West 1/16 corner between Sections 11-14. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 14). Established the corner midway and on a line of true mean bearing between monumented Section corner 1310.90' West, and monumented 1/4 corner 1310.90' East. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I recovered a 1" I.D. pipe, painted yellow, probably placed long ago by Combined Locks Company, 1.2' south and 13.4' east. I did not regard this pipe as being a careful and faithful determination of the position of the corner. Corner placed and witnessed by T.Stark and D.Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
(?) Set 1" pipe with 4" MDNR cap.

Blazed, scribed, and set measuring nails
in the following:

5" J. Pine N13E 0.5' "W1/16 BT"

5" Cedar N52E 20.8' "W1/16 BT"

6" J. Pine S45E 21.25' "W1/16 BT"

8" R. Pine S19E 5.5' "W1/16 BT"

The pipe, noted above: S80E 13.4'

Placed a location poster on a N-S trail,

West, approx. 44'. Bearings are

magnetic.

Signed by

Stephan J. Szyszkoski

Date 2-12-97

Surveyor's Michigan License No. 33986



For the Michigan Department of Natural Resources - Forest Management Division

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1973
REVISED JAN., 1983
REVISED OCT., 1986