

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey

T 50N R 7W J5

T 50N R 7W K5

T R

T R

2. Property Controlling  
In Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Oct 28 1996

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J5) Quarter corner common to Sections 11-14. Corner established in 1849 by Wells Burt: "...39.80 Set W. Pine post qr. section corner, Spruce 6 S39E 32, do 6 N42 1/2 W 72...79.80 Section corner." Found no subsequent record.

(K5) Corner common to Sections 11-12-13-14. Corner previously recorded and described by Billy D. Buckler, RLS, in 1973: "Corner replaced from one original B.T. in poor condition, N25E 39 links. Placed 1" pipe with 4" cap, 7" Jack Pine N12E 7.5', 9" J. Pine S58W 23.2'". Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J5) Original post and accessories not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on a line of true mean bearing between Section corners 2621.80' east and west. At the position for the corner, I placed a 1" I.D. x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the corner monumented, I found a 1" iron pipe, painted yellow, probably placed long ago by Combined Locks Company, 1.1' south and 20.8' east. I did not regard the pipe as being a careful and faithful reestablishment of the position of the corner, nor a perpetuation of the original corner. From the measurements, it appears to have been placed 1320' due east from a similar pipe to the west. The MDNR corner was placed and witnessed by T.Stark and D.Lampela, Newberry District Office.

(K5) Recovered the 1973 monument, as described, in good condition, and at record bearing and distance from the remaining 1973 witness 9' (now 12") J. Pine, found in good condition. The other 1973 witness is windthrown. Left the monument in place, made new marks on the 1973 NBT, and marked three new accessories as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J5) Set 1" iron pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:

16" R. Pine S83W 28.8' "1/4S NBT"  
14" J. Pine S58W 18.3' "1/4S NBT"  
7" J. Pine S28E 15.7' "1/4S NBT"  
6" J. Pine N86E 18.95' "1/4S NBT"

The pipe noted above: S82E 20.8'  
Placed a cedar post adjacent, and a location tag at E-W trail approx 170' north. Bearings magnetic.

(K5) Found 1" Pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following:

12" J. Pine S62W 23.5' "S14 NBT"  
6" Maple N50W 70.65' "S11 NBT"  
7" J. Pine S52E 14.3' "S13 NBT"  
6" W. Pine N72E 20.55' "S12 NBT"

Placed a 4" squared and scribed cedar post adjacent. Placed a location poster 360' N. on and E-W trail. Bearings are magnetic.



Signed by

*Stephan J. Szyszkoski*

Date 2-12-97

Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division