

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

Located In:

Corner Code #

1. Public Land Survey

T 50N R 7W J11
T 50N R 7W K11
T R
T R

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Oct 14 1996

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(J11) Quarter corner common to Sections 26-35. Corner established in 1849 by Wells Burt. "Set W. Pine post gr. section corner. W. Pine 12 N56E 23, S. Pine 14 S58W 29". Corner remonumented in 1952 by Dean C. DeLaWater: "This corner was pointed out to me by B. McTiver, District Forester, of Newberry. Two original B.T.'s still in place, one in good condition, one fair." Corner monument: 1" pipe with 4" Brass cap. Witnesses: 7" J. Pine S52W 14 links, 9" J. Pine S27E 30 links.
(K11) Corner common to Sections 25-26-35-36. Corner remonumented in 1952 by Dean C. DeLaWater: "...Two original B.T.'s still in place, good condition". Description of corner monument: 1" Pipe with 4" Brass cap. Witnesses to corner: 10" J. Pine N35E 35 links, 10" J. Pine S26E 20 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J11) Recovered the 1952 monument as described, in good condition, and at record bearing and distance from the 1952 witness trees, the J. Pine SW being in good condition, that SE found dead and down; and also from the remaining original B.T., S. Pine 14, found in fair condition. Left the monument in place, marked new BH blaze and set measuring nail in the remaining 1952 witness, and marked three new accessories as described below. Corner recovered and rewitnessed by T. Stark and D. Lampela, Newberry District Office.
(K11) Found the 1952 monument as described, in good condition, and at record bearing and distance from the 1952 witnesses. The J. Pine SE is dead and down, and that to the NE is dead but still standing. Left the monument in place and marked four new accessories as described below. The original B.T.s were not recovered. Corner recovered and rewitnessed by T. Stark and D. Lampela, Newberry District Office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J11) Found 1" pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in:
10" J. Pine S52W 9.05' "1/4S"
8" J. Pine N20W 8.7' "1/4S NBT"
8" J. Pine N87E 7.85' "1/4S NBT"
10" J. Pine S48E 11.4' "1/4S NBT"
Bearings are magnetic.

(K11) Found 1" pipe with 4" brass MI Dept. of Conservation cap. Blazed, scribed, and set measuring nails in:
4" Maple N79W 36.25' "S26 NBT"
8" W. Pine N68W 82.0' "S26 NBT"
4" Maple N05E 43.05' "S25 NBT"
5" W. Birch S77E 55.85' "S36 NBT"
Placed a 5" scribed cedar post adjacent.
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 2-13-97

For the Michigan Department of Natural Resources - Forest Management Division