

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>50N</u> R <u>7W</u>	<u>H12</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>34</u> T <u>50N</u> R <u>7W</u>	<u>8</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 20 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		●		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(H12) Center of Section 34. Not established in the original survey. Found no subsequent record.
 (8-Sec. 34) West 1/16 corner, Section 34. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H12) Established the corner at the intersection of straight lines connecting opposite 1/4 corners. The position for the corner falls in the Betsy River and was not monumented. Established a WITNESS CORNER to H12, on the E-W 1/4 line of the Section, 10.60' East of the position for H12. The WITNESS CORNER falls at the top of bank on the east side of the river. The monument cap is incorrectly stamped "10.95 [sic] East" but the stamped arrow points west to the corner position.
 (8-Sec. 34) Established the corner midway and on a straight line between Center of Section 1327.00' East and Quarter corner 1327.00' West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap 10.60' East of the corner position, a WITNESS CORNER to H12. Set measuring nails in: 12" Spruce S79E 17.35' mrkd "WC 8T" 12" Spruce S43E 20.6' do 12" Spruce N24W 22.2' do 7" twin Spruce N02W 27.75' do Bearings are magnetic. Distances are to nail with tag.	(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 4" J.Pine N78W 15.67' mrkd "W1/16 BT" 7" J.Pine S43W 31.78' do 14" J.Pine S36E 25.27' do 7" R.Pine EAST 31.85' do Fd. 1" pipe S17E 15.37' Bearings are magnetic. Distances to trees are to nail with tag.
---	---

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/8/04