

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>50N</u> R <u>7W</u>	J13
	T <u>50N</u> R <u>7W</u>	K13
2. Property Controlling in Section	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

K13 Oct 24 2005
 J13 Oct 25 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J13) Quarter corner common to Section 35 T50N-R07W and Section 2 T49N-R07W. 1952 - Remonumented from original B.T. by Dean C. DeLaMater RLS. Set 1" pipe with 4" brass cap. 10" J.Pine N24W 65 links, 10" J.Pine N15E 63 links.
 (K13) Corner common to Sections 35 and 36 T50N-R07W and Sectitons 1 and 2 T49N-R07W. 1952 - Dean C. DeLaMater RLS perpetuated and remonumented a position located by Marcus Schaaf RLS. Set 1" Pipe with 4" brass cap. 7" J.Pine S75E 12 links, 7" J.Pine S64W 49 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J13) Recovered the 1952 monument in good condition and at record bearing and distance from the 1952 NBTs, now both standing dead. No sign of the original Birch and Beech bearing trees. Left the monument in place and made new witnesses.
 (K13) Recovered the 1952 monument in good condition and at record bearing and distance from the 1952 NBTs: the J.Pine 7" SW, now standing dead, and the J.Pine SE now a stump. Left the monument in place and made new witnesses.

C. Description of monument for corner and accessories established to perpetuate locating the position:

(J13) Found 1" ID I. pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in: 4" J.Pine S14E 20.85' mrd "1/4S NBT" 4" J.Pine N46W 19.25' do 5" J.Pine N81W 34.7' do 6" B.Spruce N21W 46.6' do Bearings are magnetic. Distances are to nail with tag	(K13) Found 1" ID I. pipe with 4" brass MI Dept. of Conservation cap. Set measuring nails in: 5" J.Pine S10E 18.85' (dead) 7" J.Pine S58W 32.7' (dead, old blaze) * 4" J.Pine North 17.9' (dead) 3" B.Spruce N60W 37.65' no marks Bearings are magnetic. Distances are to nail with tag. * denotes 1952 NBT.
--	---



Signed by Stephan J. Szyszkoski Date 8/8/06
 Surveyor's Michigan License No. 33986