

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

| | | |
|---------------------------------------|---|-------------|
| 1. Public Land Survey | T <u>50N</u> R <u>7W</u> | <u>K12</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u>35</u> T <u>50N</u> R <u>7W</u> | <u>8</u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

K12 May 22 2006
 8 Jan 12 2006

Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

(K12) Quarter corner common to Sections 35 and 36. 1849 - Established by Wells Burt, Deputy Surveyor: North between Sections 35 and 36 ...40.00 Set S.Pine post quarter section corner. S.Pine 9 N52W 19 links, Spruce 10 N77E 25 links. ...80.00 Set Maple post corner of sections 25,26,35 & 36. Found no subsequent record.
 (8-Sec. 35) West 1/16 corner, Section 35. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K12) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner by single proportionate measurement to the original record between Section corners of record 2658.31' north and south.
 (8-Sec. 35) Established the corner midway and on a straight line between Quarter corner 1323.95' West and the intersection of 1/4 lines of Sec. 35, 1323.95' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|---|---|
| (K12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 6" Spruce S67E 50.9' mrd "1/4S NBT" 4" J.Pine N82W 17.9' do 4" twin J.Pine N44W 12.63' do 3" J.Pine N28E 46.6' do Bearings are magnetic. Distances are to nail with tag. | (8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 11" Spruce N55E 4.32' mrd "W1/16 BT" 12" Maple N57W 12.6' do 5" Balsam S70W 16.32' do 5" Balsam S35E 6.52' do Bearings are magnetic. Distances are to nail with tag. |
|---|---|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/8/06