

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Chippewa

(County)

Located In:

Corner Code #

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S 34	T 50N R 7W	10
	S 34	T 50N R 7W	11
3. Miscellaneous Property in Sec.	S	T R	_____
	S	T R	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 20 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

(10-Sec. 34) South 1/16 corner between Sections 33 and 34. Not established in the original survey. Found no subsequent record.
 (11-Sec. 34) Southwest 1/16 corner, Section 34. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(10-Sec. 34) Established the corner midway and on a straight line between Section corner 1314.92' south and Quarter corner 1314.92' north.
 (11-Sec. 34) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 8" W.Pine N39E 6.55' mrkd "S1/16 BT" 8" W.Birch N17W 18.22' do 5" W.Birch N60W 8.4' do 4" Maple S21W 4.55' do Fd. 1" pipe N21E 26.8' (slope dist). Bearings are magnetic. Distances to trees are to nail with tag.	(11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 4" Balsam S56E 23.9' mrkd "SW1/16 BT" 12" Spruce S22E 18.1' do 10" Cedar S02E 18.5' do Fd. 1" pipe S22W 13.09' Bearings are magnetic. Distances to trees are to nail with tag.
---	--



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/8/06