

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>7W</u>	<u>E12</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32	●	33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 10/27/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E12) Quarter corner common to Sections 32 and 33. 1849 - Established by Wells Burt Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains north and south. Set spruce post. W.Pine 10" S36W 26 links, Spruce 8" N30E 16 links. 1952 - Remonumented by D.C.DeLaMater RLS, in the original position, at record bearing and distance from "one original B.T. still in place, down, good condition". Set 1" pipe with 4" brass cap. 10" W.Pine N80E 36 links, 8" Jack Pine S40W 54 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E12) Found the 1952 monument in good condition and at record bearing and distance from the 1952 witnesses. The W.Pine NE is in good condition with no visible marks, the J.Pine SW is standing dead with markings visible. The original B.T.s were not recovered. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E12) Found 1" ID I. pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 19" W.Pine N85E 23.66' mrkd "1/4S" 1952 NBT
 11" J.Pine N64W 14.85' mrkd "1/4S NBT"
 6" Spruce S33W 6.57' do
 8" R.Pine S48E 29.35' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 01/27/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities