

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 33 T 50N R 7W	F12
	S 33 T 50N R 7W	1
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 1 10/19/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F12) Center of Section 33. Not established in the original survey.

(1-Sec. 33) West 1/16 corner between Sections 28 and 33. 1975 - Established by Billy D. Buckler RLS midway and on line between Section corner to West and Quarter corner to East. Set 1"ID I.pipe with 4" alum. cap. 18" R.Pine N53W 64.5', 8" J.Pine N60E 21.4'. In his recordation of this corner, Mr. Buckler incorrectly described it as being 1/16 corner #1, Section 28. It should have been described as 1/16 corner #15, Section 28, or #1, Section 33.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F12) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

(1-Sec. 33) Found the 1975 monument in good condition, substantially at the record position between adjacent government corners, and at record bearing and distance from the 1975 witnesses, both still in good condition. Accepted the monument as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F12) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" J.Pine S19E 72.7' mrkd "CS BT"
 6" J.Pine S45E 14.15' do
 11" R.Pine N83E 60.04' do
 Found 1" pipe N74E 1.64'
 Bearings are magnetic.

(1) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 26" R.Pine N53W 65.22' mrkd "W1/16" 1975 BT
 12" J.Pine N60E 21.2' do do
 8" twin Oak N14E 18.1' mrkd "W1/16 BT"
 6" W.Pine S18E 6.73' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 01/27/2010

For the Michigan Department of Natural Resources, Office of Land and Facilities

