

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 50N R 7W	F11
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 10/19/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F11) Quarter corner common to Sections 28 and 33. 1849 - Established by Wells Burt Deputy Surveyor, midway and on the Section line between Section corners 39.95 chains east and west. Set S.Pine post. W.Birch 8" N45E 23 links, S.Pine 7" S51W 36 links. 1975 - Billy D. Buckler RLS, found no evidence of the original corner and reestablished the corner by single proportionate measurement to the original record between Section corners. Set 1" pipe with 4" aluminum cap. 18" R.Pine N86E 74.2', 8" J.Pine S10E 11.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F11) The original post and accessories were not recovered. Found the 1975 monument in good condition and at record bearing and distance from the 1975 NBT R.Pine NE, in good condition. The 1975 NBT J.Pine was not recovered. Verified the position of the monument as being 0.28' east and 0.97' south of the proportionate position intended in 1975 and I accept the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F11) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 21" R.Pine N85E 74.15' mrkd "1/4S" 1975 NBT
 10" J.Pine N18W 17.9' mrkd "1/4S NBT"
 5" J.Pine N09E 48.23' do
 5" J.Pine S20W 19.38' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 01/27/2010
 Surveyor's Michigan License No. 33986