

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>7W</u>	<u>E11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 06/16/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E11) Corner common to Sections 28-29-32-33. 1849 - Established by Wells Burt Deputy Surveyor. Set spruce post. Y.Pine 14" S07W 124 links, Y.Pine 14" N77E 141 links. 1952 - Remonumented in the original position by D.C.DeLaMater RLS from one original B.T., still in place, [Y.Pine S07W 124 links] excellent condition. Set 1" pipe with 4" brass cap. 14" R.Pine S11E 90 links, 18" R.Pine S72E 98 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E11) Found the 1952 monument in good condition and at record bearing and distance from the 1952 witnesses. The Red Pine S11E is in good condition, the Red Pine S72E is dead. Also recovered the stump remains of the original B.T. Y.Pine S07W 124 links, old blaze visible, at record bearing and distance. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E11) Found 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 18" R.Pine S10E 59.2' mrkd "S33" 1952 NBT
 7" W.Pine N38W 42.3' mrkd "S29 NBT"
 8" B.Spruce S61W 5.6' "S32 NBT"
 14" R.Pine S53E 45.75' "S33 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 01/27/2010
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities