
## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Chippewa	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T R T R		
2. Property Controlling in Section	S 27 T 50N R 7W S T R S T R	H10	
<ol><li>Miscellaneous Property in Sec.</li></ol>	S T R R		Register of Deeds Stamp & File Number
4. Lot No. , Re	ecorded Plat		ABCDEFGHTJ
5. Private Claims			2 6 5 4 3 2
ı, Stephan J. Szyszkoski ,	in a field survey on 10/29/	/2008 do hereby state	

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey 5 instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of 6 a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with 7 the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, g re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



(H10) Center of Section 27. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H10) Established the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 10" R.Pine N54W 12.93' mrkd "CS BT" 7" J.Pine S63W 30.12' do 10" J.Pine S31W 50.82' do 18" W.Pine S53E 18.08' do Bearings are magnetic.



Date

11/18/2008

10