

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Chippewa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 50N R 7W	H9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 09/18/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H9) Quarter corner common to Sections 22 and 27. 1849 - Established by Wells Burt Deputy Surveyor. Set maple post midway and on the Section line between Section corners 40.03 chains east and west. W.Pine 24" S85W 21 links, W.Pine 10" N73E 24 links. 1960 - Remonumented by Billy D. Buckler RLS at record bearing and distance from the original W.Pine B.Ts. The BT SW was found as a high-cut stump, the BT NE down and in fair condition. Set 1" I.pipe with 4" brass cap. 5" J.Pine S06E 56 links, 18" R.Pine S57E 152 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H9) Recovered the 1960 monument in good condition and at record bearing and distance from the 1960 NBTs. The J.Pine SE is a stump, the R.Pine SE is in good condition. Also recovered the remains of the original BTs at record bearing and distance: The W.Pine SW is a stump with blaze and notch visible, the W.Pine NE is a rotted stump. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H9) Fd. 1" ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 6" J.Pine N12E 25.7' mrkd "1/4S NBT"  
 12" J.Pine S73E 9.45' do  
 8" J.Pine N69W 17.35' do  
 7" W.Pine S22W 49.6' do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/18/2008  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities