

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Chippewa</u> <small>(County)</small>	Located In:	Corner Code #	
1. Public Land Survey	T <u>50N</u> R <u>7W</u>	<u>G9</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on 09/22/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G9) Corner common to Sections 21-22-27-28. 1849 - Established by Wells Burt Deputy Surveyor. Set W. Pine post. Y.Pine 20" S29W 57 links, Y.Pine 14" N56E 60 links. 1952 - Remonumented by Dean C. DeLaMater RLS at record bearing and distance from two original B.T.s still in place, one fair condition, one poor. Set 1"ID I.pipe with 4" brass cap. 8" J.Pine N39W 22 links, 10" J.Pine S52E 68 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G9) Recovered the 1952 monument in good condition and at record bearing and distance from the 1952 NBTs. The J.Pine NW is in good condition. The J.Pine SE is standing dead. The stump of the original BT Y.Pine N56E is still in place, at record bearing and distance, with old blaze visible. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G9) Fd. 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 12" J.Pine N37W 14.9' mrkd "S21" 1952 NBT
 5" J.Pine N65E 13.55' "S22 NBT"
 12" J.Pine S15E 13.3' "S27 NBT"
 8" J.Pine S89W 23.35' "S28 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 11/18/2008
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities