

SURVEY & REMONUMENTATION

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

CLARE COUNTY REMONUMENTATION

20000009723

Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULAY
On 11-29-2000 At 12:12 PM.
LAND CORNER 9.00
OR Liber 2 Page 252 - 252

SECTION

For Corners in: Clare Located In _____ Corner Code # _____
(County)

1. Public Land Survey	T	<u>17N</u>	R	<u>5W</u>	<u>D12</u>
	T		R		
2. Property Controlling in Section	S	T	R		
	S	T	R		
3. Miscellaneous Property in Section	S	T	R		
	S	T	R		

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on August 8, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Instrument _____ Liber Page _____
20000009723 OR 2 252

457-00

Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

D12-None

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul S. Lipton
Date 10-25-00

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

D12-C 1/4, Sec. 32 - Set 3 1/2" DNR Aluminum Cap on 1" x 36" Galv. Iron Pipe at intersection of 1/4 lines in swamp. DNR Mon. accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D12-DNR Monument. Add Ring of Stone

Set Blue Carsonite Post w/ Loc. Tag 1' NE
N27°W 20.39' to N&T in W. side 9" Cedar scribed 'XBT'
N64°W 26.74' to N&T in S. side 8" Hemlock scribed 'XBT'
S14°W 41.54' to N&T in W. side 11" Cedar scribed 'XBT'
N32°E 35.48' to N&T in W side 8" R. Maple scribed 'XBT'

DNR Mon. used & accepted in place of Clare Co. Remon. Mon.



Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 10/18/2000