

**JAN 23 2001**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. PA 1970  
CLARE COUNTY REMONUMENTATION

**SECTION**

| For Corners In:<br>Clare<br>(County) | Located In               | Corner Code # |
|--------------------------------------|--------------------------|---------------|
| 1. Public Land Survey                | T <u>17N</u> R <u>5W</u> | <u>E12</u>    |
|                                      | T _____ R _____          | _____         |
| 2. Property Controlling in Section   | S _____ T _____ R _____  | _____         |
|                                      | S _____ T _____ R _____  | _____         |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____  | _____         |
|                                      | S _____ T _____ R _____  | _____         |
| 4. Lot No: _____                     | Recorded Plat: _____     |               |
| 5. Private Claims: _____             |                          |               |

20000009724  
Filed for Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 11-29-2000 At 12:12 PM.  
LAND CORNER 9.00  
OR Liber 2 Page 253 - 253  
*# 458-00*  
Instrument \_\_\_\_\_ Liber Page  
20000009724 OR 2 253  
*# 458-00*  
Register of Deeds Stamp & File Number

I, Craig W. McVean, in a field survey on August 7, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

**A. Description of original monument and accessories and/or subsequent restoration:**

E12-GLO-Set 1/4 post-H. Nicholson-1837  
Cedar 9" S64°E 37 L.  
Cedar 8" N19°W 27 L.  
-CSR-BK.6, P. 32 & 33-  
WPS 18" NE 17.5 L  
Poplar 3" E 26 L.

**APPROVED LAND CORNER**  
P.A. 345 of 1990  
Clare County  
Chairman *[Signature]*  
Date 10-25-00

**B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:**

E12-1/4 Corner common to Sec. 32 & 33- Couldn't find any GLO or CSR evidence. Set 4" DNR Alum. Cap on 1" x 4' Long Galv. Iron Pipe by Single Proportion between E11 & E13. DNR Mon. accepted as a careful & faithful re-establishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E12-DNR Monument  
Set Blue Carsonite Post w/ Loc. Tag 1'NE  
N67°W 24.22' to N&T in NE side 8" R. Maple scribed 'XBT'  
N10°E 81.45' to N&T in E side 8" Cedar  
S5°E 49.59' to N&T in W side 9" Tw. W. Pine scribed 'XBT'  
S70°E 52.38' to N&T in N side 30" W. Pine scribed 'XBT'

DNR Mon. used & accepted in place of Clare Co. Remon. Mon.



Signed by: *Craig W. McVean*  
Surveyor's Michigan License No.: 39088

Date: 10/18/2000