

SURVEY & REMONUMENTATION

JAN 23 2001

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

SECTION

CLARE COUNTY REMONUMENTATION 20000009711

For Corners in: Clare (County)	Located In	Corner Code #
1. Public Land Survey	T 17N R 5W	H12
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Section	S T R	

Filed for Record in
CLARE COUNTY MICHIGAN
CAROL MCAULLAY
On 11-29-2000 At 12:12 PM.
LAND CORNER 9.00
OR Liber 2 Page 240 - 240

Instrument 200000009711 OR Liber Page 2 240

445-00

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____
5. Private Claims: _____

I, Craig W. McVean, in a field survey on July 17, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
H12-Rec. Sur. L.2, P.203-M. McClung-1975
Fd. corner by Lapham & Assoc.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman *Paul D. Lapham*
Date 8-23-2000

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:
H12- Center 1/4, Sec. 34-Fd. 1/2" x 18" capped Rebar #9433-1.35' S & 0.01' E of calculated 1/4 line intersection. CL of 2 track is 10' SE'ly. Barbwire fence diagonal is 50'+ SE'ly. CIR #9433 accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H12-Replaced 1/2" x 18" CIR #9433 w/ 3 1/2" DNR Alum. Cap on 1" x 36" Galv. Iron Pipe. Set Blue Carsonite Post 1' NW
N42°W 23.10' to N&T in SW side 7" R. Oak scribed 'XBT'
N33°E 16.62' to N&T in W side 3" R. Oak scribed 'XBT'
N67°E 47.54' to N&T in NW side 6" R. Maple scribed 'XBT'
S12°W 77.25' to N&T in E side 6" R. Pine scribed 'XBT'

DNR Mon. used & accepted in place of Clare Co. Remon. Mon.



Signed by: *Craig W. McVean*
Surveyor's Michigan License No.: 39088

Date: 10/18/2000