

MAR 24 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Clare County Remonumentation

For Corners in

<u>Clare</u> (County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>17N</u> R. <u>5W</u>	<u>K-5</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

199900009789  
Filed for Record in  
CLARE COUNTY MICHIGAN  
CAROL MCAULAY  
On 11-10-1999 At 01:30 pm.  
LAND CORNER 9.00  
OR Liber 2 Page 68 - 68

Instrument 199900009789 OR Liber 2 Page 68

# 379-99

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on June 30, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1837 Nicholson  
Set Post Cor. Sec 11, 12, 13, 14  
Beech 6" S24E 07  
Beech 8" N89W 17

1916 Unknown, C.S.R. 6- 11, 12, 13, & 14  
W. Pine Stb. 20" S56 1/2 W 65  
W. Pine Stp. 16" N55W 64

1970 MSHD, Project #18024  
Fd large bolt with remains of tile & cinders around.  
Raised with 3/4" x 14" pipe.  
Cor 2' S. of N. edge trail  
N56E 24.26 18" Poplar  
N88E 26.38 8" Birch  
S32E 54.59 11" Poplar  
S53W 30.88 11" Tw. Birch  
Meas. W. 2669.90  
Meas. S. 2628.73

1975 Myers, (132) 1-987 & LCRC #208  
Fd 3/4" Pipe  
Same as 1970 MSHD survey  
Meas. W 2669.46

1988 Lapham  
Same as (132) 1-987

1991 Robison  
Same as (132) 1-987

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

See dossier for detailed report.

Found 1 1/2" square bolt in 3" tile 1 1/2 feet below surface. Found two 1970 witnesses and stumps of remaining two. Corner is 150 feet north of service road and 50 feet east of N-S gravel drive. Meas. West 2669.25 to J-5.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

Set 5/8" x 36" re-rod with Clare Co. Remon Cap marked P.S. #27458 in 3" tile. Accepted as best available evidence of the perpetuation of the C.S.R. Corner.

Witnesses:

N82°E 72.47 Set N & T in 10" W. Pine  
N30°E 5.96 Set N & T in 2" Oak  
S20°E 36.32 Set N & T in 3" W. Pine  
S25°W 16.43 Set N & T in 6" W. Pine



APPROVED LAND CORNER

P.A. 345 of 1990

Clare County

Chairman *Paul D. Lepson*

Date 9-29-99

Signed by *Mark R. Robison*  
Surveyor's Michigan License No. 27458

Date 11-8-99