

**SURVEY &
REMONUMENTATION**

MAR 24 2000 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
SECTION Clare County Remonumentation

For Corners in
Clare

(County)	Located In:	Corner Code#:
1. Public Land Survey	T. <u>17N</u> R. <u>5W</u>	<u>K-6</u>
	T. _____ R. _____	_____
	T. _____ R. _____	_____
2. Public Controlling in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
3. Miscellaneous Property in Section	S. _____ T. _____ R. _____	_____
	S. _____ T. _____ R. _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

199900010465
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 12-03-1999 At 02:36 pm.
 LAND CORNER 9.00
 OR Liber 2 Page 103 - 103

Instrument Liber Page
 199900010465 OR 2 103

391-99

Register of Deeds Stamp & File Number

9-23-99

I, Mark R. Robison, in a field survey on A do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

1837 Nicholson
 Set 1/4 Sec Post
 Cedar 8" S38E 05
 Cedar 9" N23W 07

1916 Unknown, CSR 6-13 & 6-14
 Tgle & cinders & stake
 Cedar 8" S9W 42

1970 MSHD Project #18024
 Fd tile remains & lightning rod below surface of water, raised with 3/4" pipe 0.6'
 North of fence line S & 55' N of fence line East
 S30E 9.14 7" Tamarack
 S25W 21.62 8" Cedar
 S65W 40.60 11" Cedar

1975 Meyers, (132) 1-991
 Fd 1" Pipe in 3" Tile
 Same witnesses as MSHD

1975 Lapham LCRC #208
 Same as (132) 1-991

1982 Lapham Unrec Survey
 Fd 1" Pipe in 3" Tile
 S30E 9.14 7" Tamarack
 S25W 21.62 8" Cedar
 S65W 40.60 11" Cedar

1986 Lapham, (132) 2-614
 Found 3/4" pipe in tile
 S10 W 21.60 12" Cedar
 South 0.60 Fence Post
 S20E 9.25 10" Tamarack

1990 Robison, (132) 3-173
 Same as 1982 unrecorded survey

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

See dossier for detailed report.

Found 3/4" x 48" pipe in 3" clay tile. Found one MSHD witness and one 1986 witness and fence line South. Corner falls in edge of water.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" re-rod with Clare Co. Remon Cap marked P.S. #27458 in tile. Accepted as best available evidence of the perpetuation of the CSR corner.

Witnesses:
 S88°E 7.00 N & T in 4" Cedar
 S15°E 21.70 N & T in 6" Cedar
 N45°W 0.40 Steel fence post
 S30°E 9.14 N & T in 10" Tamarack (OBT)

APPROVED LAND CORNER

P.A. 345 of 1990

Clare County

Chairman Carol McAulay

Date 9-29-99

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458



Date 12-3-99