

**MAR 24 2000**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**Clare County Remonumentation**

For Corners in  
Clare

(County)

Located In:

Corner Code#:

- 1. Public Land Survey T. 17N R. 5W K-7  
 T. \_\_\_\_\_ R. \_\_\_\_\_  
 T. \_\_\_\_\_ R. \_\_\_\_\_
- 2. Public Controlling S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
 in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 3. Miscellaneous S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_  
 Property in Section S. \_\_\_\_\_ T. \_\_\_\_\_ R. \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

199900009781  
 Filed for Record in  
 CLARE COUNTY MICHIGAN  
 CAROL MCAULAY  
 On 11-10-1999 At 01:30 pm.  
 LAND CORNER 9.00  
 OR Liber 2 Page 60 - 60

Instrument 199900009781 OR Liber 2 Page 60

#371-99

**Register of Deeds Stamp & File Number**

I, Mark R. Robison, in a field survey on 9-22-99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

1837 Hodson  
 Hemlock 24" Cr. Sec. 13, 14, 24, 23

Circa 1900, Unknown, CSR 6-13 & 14  
 Tile & Cinders  
 Cedar F. Post 6 550

Circa 1965 M.S.H.D, U.S. 10 R/W Plan 18024  
 Fd. 60 Penny Nail on line W/N-S Fence  
 S05W, 34.02 Cor. Fe. Post  
 S65E 80.50 31" Elm  
 N40E 94.90 S.E. Cor Hse  
 Due N 43.39 P. Pole  
 Meas. West 2640.69 to J-7

8-2-73 Lapham, (132) 1-573  
 Fd 3/4" bolt  
 S70W 100.7 18" Maple  
 N60W 73.2 18" Elm

11-6-73 Lapham LCRC #118  
 Same as (132) 1-573

5-7-75 Meyers, (132) 1-991  
 Fd. Mon. Box  
 North 29.90 Fence Cor  
 South 34.05 Fence Cor  
 S45W 43.50 2nd Post West  
 Meas. West 2640.69

8-20-75 Lapham LCRC #208  
 Same as (132) 1-991

11-30-76 Lapham, (132) 2-385  
 Same as (132) 1-573

5-10-89 Lapham, (132) 3-125  
 Same as (132) 1-991

4-13-87 Lapham  
 Same as (132) 1-991

7-22-91 Robison, (132) 3-307  
 Meas. West 2640.69 to J-7

Plats of Subdivision:  
 Reiss Sub. No. 2  
 Cut-off Road Subdivision

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

See dossier for detailed report.

Found 5/8" x 18" rered in Mon. Box 2' N of C.L. Found two 1965 witnesses and one 1975 witness. Fence line N & S.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set 5/8" x 36" rered with Clare Co. Remon Cap marked P.S. #27458 in existing Mon. Box. Accepted as best available evidence of the accepted position of the corner.

**Witnesses:**

South 35.20 N & T in Cor. F. Post  
 North 33.88 N & T in Cor. F. Post  
 S85°W 148.80 N & T in 36" Maple  
 N73°E 129.46 N & T in P. Pole  
 North 43.38 C.L. P. Pole (OBT)

Signed by Mark R. Robison  
 Surveyor's Michigan License No. 27458



**APPROVED LAND CORNER**  
 P.A. 345 of 1990  
 Clare County

Chairman Paul S. Lapham  
 Date 9-29-99

Date 11-8-99