

**SURVEY &
REMONUMENTATION**

MAR 24 2000

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Clare County Remonumentation**

For Corners in
Clare

(County)

Located In:

Corner Code#:

1. Public Land Survey T. 17N R. 5W L-7
 T. _____ R. _____
 T. _____ R. _____
 2. Public Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____
 3. Miscellaneous S. _____ T. _____ R. _____
 Property in Section S. _____ T. _____ R. _____
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

199900009782
 Filed for Record in
 CLARE COUNTY MICHIGAN
 CAROL MCAULAY
 On 11-10-1999 At 01:30 pm.
 LAND CORNER 9.00
 DR Liber 2 Page 61 - 61

Instrument Liber Page
 199900009782 DR 2 61

372-99

Register of Deeds Stamp & File Number

I, Mark R. Robison, in a field survey on September 22, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1837 Hodson
 Set 1/4 Sec. Post
 Hemlock 8 S11W 12
 Hemlock 6 N88E 10

Circa 1900 Unknown, CSR 6-13
 Cedar F. Post 6 - S42W 53 1/2
 Cedar F. Post 6 - N42 1/2W 53

7-11-63 McClung, Liber 7 Pg. 10
 Plat of Pleasant View Acres
 Conc. Mon 33.00' South

10-20-80 Lapham
 Fd Iron
 North 40.5 Jack Pine
 N30E 55.0 Jack Pine
 S30E 36.3 Fence Post
 South 33.00 Conc. Mon

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 See dossier for detailed report.

Found 1" x 1" x 18" angle iron in Mon. Box at corner and concrete monument 32.7' South and Fence Post S26E 36.30. Meas. East 2796.86 to M-7. Meas. West 2662.96 to K-7. Fence line to South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" rerod with Clare Co. Remon Cap marked P.S. #27458 in Mon. Box. Accepted as best available evidence of the accepted position of the corner.

Witnesses:

N09°W 42.32 N & T in 7" Spruce
 South 32.70 Conc. Monument (OBT)
 S26°E 36.30 N & T in Fence Post (OBT)
 N48°E 57.58 N & T in 4" Spruce



APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul B. Lapham
 Date 9-29-99

Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 11-8-99