

JAN 17 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CLARE (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>5W</u>	<u>M-6</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED
95-136-95
DEC 15 PM 3:30
REGISTER OF DEEDS
CLARE COUNTY
DOMINA M. CARR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on NOVEMBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1837 JOHN HUDSON
18" CEDAR AT CORNER

NO DATE NO SURVEYOR
TYLE & CINDERS, CEDAR STUMP 12 N81°W 26
M.S.H.D. FOUND 4" TILE OVER 3" TILE & CINDERS
SET 3/8" ROD

2-72 PAUL LAPHAM (132 SURVEY)
NO WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8"x30" IRON IN 4" CLAY TILE. REPLACED IRON WITH 5/8"x36" IRON, LEFT THE CLAY TILE.
FOUND M.S.H.D. WITNESSES.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman *Paul B. Lapham*

Date 12-12-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6: EAST 1/4 CORNER, SECTION 13
SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT CAP IN OLD 4" CLAY TILE.
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE PERPETUATION OF THE C.S.R. CORNER.

WITNESSES:
S87°E 29.97' - NAIL & TAG IN 10" CEDAR (OBT)
N68°E 37.54' - NAIL & TAG IN 8" CEDAR (OBT)
WEST 28.30' - NAIL & TAG IN 8" CEDAR
S40°E 34.30' - NAIL & TAG IN 12" ELM



Signed by Mark R. Robison
Surveyor's Michigan License No. 27458

Date 12-13-95