

JAN 17 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>5W</u>	<u>M-8</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

RECEIVED
 E 17 11 01 A L L
 95 DEC 15 9 30
 REGISTER OF DEEDS
 CLARE COUNTY
 DONNA M. CARR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, MARK R. ROBISON, in a field survey on OCTOBER, 19 95 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 JOHN HUDSON
 WIT.-HEMLOCK 7" S59°W 9
 HEMLOCK 7" N65°W 11

10-91 MARK ROBISON
 FOUND IRON, SET CAPPED IRON
 WIT.-N40°E 59.0' 5" POPLAR
 N45°W 29.39' 2nd POST FENCE NORTH
 WEST 25.97' END POST FENCE SOUTH
 S30°W 41.0' 4th POST FENCE SOUTH

NO DATE OR SURVEYOR (C.S.R.)
 WIT.-W.P. STUMP 18, N25°E 48 1/2
 W.P. STUMP 16, N72°E 46

6-21-73 URBANIAK (132) SURVEY
 FOUND TILE IN FENCE CORNER (FIELD NOTES)

9-5-74 MCCLUNG PLAT OF THE MEADOW, RECORDED PLAT

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND TILE IN FENCE CORNER 26' WEST OF CORNER REC. IN 10-91 L.C.R.C.
 FOUND & REMOVED C.I. #21781 ± 0.5' E OF TILE. CORNER REC IN 10-91 L.C.R.C. IS IN ERROR AND IRON WAS REMOVED.

APPROVED LAND CORNER
 P.A. 345 of 1990
 Clare County

Chairman Paul B. Lyle

Date 12-12-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8: EAST 1/4 CORNER, SECTION 24
 SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT IN 3" TILE.
 ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE PERPETUATION OF THE C.S.R. CORNER.

WITNESSES:
 EAST 33.6' CAPPED IRON #21781
 N45°E 3.55' FOUND SPIKE IN 24" CHERRY
 N50°W 52.00' - NAIL & TAG IN 17" OAK
 SOUTH 68.50' - NAIL & TAG IN 15" CHERRY



Signed by Mark R. Robison
 Surveyor's Michigan License No. 27458

Date 12-13-95