

SURVEY & REMONUMENTATION

JAN 17 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

RECEIVED
E 11 10 A D
95 # 132-95
DEC 15 PM 3:39
REGISTER OF DEEDS
CLARE COUNTY
NONNA M. GARR

<u>CLARE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>5W</u>	<u>M-10</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MARK R. ROBISON, in a field survey on OCTOBER, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1837 JOHN HUDSON
WIT.-BEECH 19" IS CORNER

NO DATE OR SURVEYOR, CSR
TYL. CINDERS & STAKE AT INTERSECTION OF FENCES
W.P. STUMP 30" S71°E 19

PAUL LAPHAM, (132) SURVEY
FOUND 1 1/2" PIPE IN TILE
WIT.-EAST 33.78' 36" ELM
S20°W 100.45' METER POLE
WEST 28.51' FENCE POST

6-73 LEONARD URBANIAK, (132) SURVEY
NO WITNESSES

1-74 PAUL LAPHAM, L.C.R.C.
FOUND 1 1/2" PIPE IN 3" TILE
WIT.-EAST 33.78' 36" ELM
S20°W 100.45' METER POLE
WEST 28.51' FENCE POST

5-75 PAUL LAPHAM, (132) SURVEY
SAME AS ABOVE

5-75 PAUL LAPHAM, (132) SURVEY
SAME AS ABOVE

12-94 MARK ROBISON (132) SURVEY
FOUND 1 1/2" PIPE IN 3" TILE
SAME AS ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1 1/2"x32" PIPE IN 3" CLAY TILE PER C.S.R. NOTES.
FOUND OLD ELM WITNESS. METER POLE HAS BEEN REPLACED WITH NEW POLE.

APPROVED LAND CORNER
P.A. 345 of 1990
Clare County

Chairman Paul R. Robison

Date 12-12-95

This Corner established in Clare County Remonumentation Program.

See dossier for detailed report.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 EAST 1/4 CORNER, SECTION 25
SET 5/8"x36" RE-ROD WITH 3" CLARE COUNTY MONUMENT
ACCEPTED AS BEST AVAILABLE EVIDENCE OF THE PERPETUATION OF THE C.S.R. CORNER

WITNESSES:
EAST 33.78' - NAIL & TAG IN 38" ELM (OBT)
S20°W 101.50' - NAIL & TAG IN NEW METER POLE
N75°W 68.94' - NAIL & TAG IN 20" SPRUCE
S30°E 97.96' - NAIL & TAG IN 14" RED PINE



Signed by Mark R. Robison

Date 12-13-95

Surveyor's Michigan License No. 27458