

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Clare (County)	Located In	Corner Code #
1. Public Land Survey	T <u>17N</u> R <u>5W</u> E <u>12</u>	T _____ R _____
2. Property Controlling in Section	S _____ T _____ R _____	S _____ T _____ R _____
3. Miscellaneous Property in Section	S _____ T _____ R _____	S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on August 7, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32	●	33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E12-GLO-Set 1/4 post-H. Nicholson-1837
 Cedar 9" S64°E 37 L.
 Cedar 8" N19°W 27 L.
 -CSR-BK.6, P. 32 & 33-
 WPS 18" NE 17.5 L
 Poplar 3" E 26 L.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

E12-1/4 Corner common to Sec. 32 & 33- Couldn't find any GLO or CSR evidence. Set 4" DNR Alum. Cap on 1" x 4' Long Galv. Iron Pipe by Single Proportion between E11 & E13. DNR Mon. accepted as a careful & faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E12-DNR Monument
 Set Blue Carsonite Post w/ Loc. Tag 1'NE
 N67°W 24.22' to N&T in NE side 8" R. Maple scribed 'XBT'
 N10°E 81.45' to N&T in E side 8" Cedar
 S5°E 49.59' to N&T in W side 9" Tw. W. Pine scribed 'XBT'
 S70°E 52.38' to N&T in N side 30" W. Pine scribed 'XBT'

DNR Mon. used & accepted in place of Clare Co. Remon. Mon.



Signed by: Craig W. McVean
 Surveyor's Michigan License No.: 39088

Date: 10/18/2000