

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | |
|---------------------------------------|--------------------------------------|---------------|
| <u>Clare</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>29</u> T <u>17N</u> R <u>5W</u> | <u>2</u> |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on June 26, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

2 - none

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

2 - E 1/16 Cor. common to Sec. 20 & 29, T17N, R5W
 Set 2" Alum. Cap on 5/8" X 34" rebar per standard BLM procedure. C/L of E-W Gravel RD. is 3' +/- N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2 - 2" AC on 5/8" X 34" Rebar - down 0.7'
 South 33.01' to Fd. 1/2" CIR # 9433 & add Blue Carsonite Post with Loc. Tag.
 N1°W 77.05' to N&T in W. side 30" R. Oak
 N31°E 60.23' to N&T in NW side 8" R. Oak
 S51°W 63.62' to N&T in SE side 14" S. Maple



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 10/18/2000