

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Clare (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
2. Property Controlling in Section	S 29 T 17N R 5W	10
	S 29 T 17N R 5W	13
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Craig W. McVean, in a field survey on August 10, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

10 - DNR Sur. Proj. # 02-5564
K.J. Ostling - 1980
Fd. 5/8" Iron Rod

13 - none



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

10 - S 1/16 Cor. common to Sec. 29 & 30
Fd. Bent 5/8" X 18" Rebar per Ostling Survey
in C/L N-S Gravel Rd. Fence line E is 7.5' +/- S.
Bent 5/8" Rebar accepted as the best available
evidence of the position of the corner.

13-SE 1/16, Sec. 29, T17N R5W
Set 2" Aluminum Cap on 5/8" x 34" Rebar per Standard
BLM Procedure - down 0.5' - with ring of stone. In SW'ly
edge of sand 2-track NW-S'y.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10 - Replaced bent 5/8" X 18" rebar with 2" Alum. Cap on
5/8" X 34" rebar.
East 33.00' to set 2" Alum. Cap on 5/8"x34"
Rebar on line with Blue carsonite post with Loc. Tag.
S16°E 59.60' to N&T in W. side 7" Ash
N64°E 30.14' to N&T in SE side 1" R. Oak
West 33.00' to Fd. 3/4" iron rod.

13-Set 2" AC on 5/8" x 34" Rebar- down 0.5'- with ring of stone.
N85°W 43.92' to N&T in S. side 4" R. Oak
N13°W 56.68' to N&T in E side 7" W. Pine
N30°E 48.15' to N&T in NW side 6" W. Pine
N82°E 64.86' to N&T in N side 5" R. Oak
Set Blue Carsonite Post w/ Location Tag 15' S

Signed by: Craig W. McVean
Surveyor's Michigan License No.: 39088

Date: 10/18/2000