

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Clare Located In \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

- |                                      |             |              |             |  |                |
|--------------------------------------|-------------|--------------|-------------|--|----------------|
| 1. Public Land Survey                | T _____     | R _____      |             |  |                |
|                                      | T _____     | R _____      |             |  |                |
| 2. Property Controlling in Section   | S <u>32</u> | T <u>17N</u> | R <u>5W</u> |  | <u>16</u>      |
|                                      | S <u>32</u> | T <u>17N</u> | R <u>5W</u> |  | <u>EE 1/64</u> |
| 3. Miscellaneous Property in Section | S _____     | T _____      | R _____     |  |                |
|                                      | S _____     | T _____      | R _____     |  |                |

Register of Deeds Stamp & File Number

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Craig W. McVean, in a field survey on August 10, 2000 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

16- None EE 1/64 - none



B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

<p><u>16- E 1/16 on S. Line Sec. 32, T17N, R5W</u>                  Set 2" Aluminum Cap on 5/8" x 34" Rebar per Standard BLM Procedure. CL of E-W 2-Track is 10' N. E-W Barb Wire Fence is 14' S. E-W Single Strand fence is 30' N.</p>	<p><u>EE 1/64 on S. line Sec. 32- SE Cor. of W 1/2 of E 1/2 of SE 1/4 Sec. 32 - Set 2" Alum. Cap on 5/8" X 34" Rebar per standard BLM procedure. CL of E-W 2 Track through swamp is 18' N. South E-W Lane Fence 1' N.</u></p>
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><u>16- Set 2" AC on 5/8" x 34" Rebar.</u>                  S2°E 9.83' to N&amp;T in W. side 6" R. Oak                  S72°E 20.71' to N&amp;T in SW side 3" R. Maple                  N27°E 37.29' to N&amp;T in E side 6" Fir                  N48°W 41.82' to N&amp;T in NE side 8" R. Oak                  Set Blue Carsonite Post w/ Location Tag 1' NE</p>	<p><u>EE 1/64 - 2" Alum. Cap on 5/8" X 34" Rebar</u>                  N16°E 41.59' to S&amp;T in W. side 12" Cedar                  S 60°E 22.86' to N&amp;T in N. side 12" Cedar                  S 53°W 18.71' to N&amp;T in SE. side 7" R. Cedar                  N 70°W 7.29' to N&amp;T in S side 8" R. Maple                  Set Blue Carsonite Post w/ Loc. Tag 1" NW</p>
---	---

Signed by: Craig W. McVean  
 Surveyor's Michigan License No.: 39088

Date: 10/18/2000