

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Clare</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 17N R 5W	K9
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Num

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Craig W. McVean, in a field survey on Aug. 26, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- K9 - GLO - Set Post - H. Nicholson - 1837
 Sugar 18" S69°W 17 L.
 Sugar 8" N41°E 5 L.
 Rec. Sur. L.1, P.107-1972;
 L.2, P.691-1981, L.3, P.756-1998
- County Survey Record, L. 6, p. 24 & p. 626.
 Tele pole 10" S 28° E 89 Links
 Fence post 6" S 28.5° W 53 Links
- 1972, P. Lapham, LCRC #29-72.
 Power pole S 20° E 26.6'
 Forker Cedar N 88° W 88.0'
- 1977, P. Lapham, LCRC #306-77, 3/4" sucker rod.
 (same witness as above)
 Power pole S 80° E 104.78'
 Power pole N 80° E 111.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K9 - Sec. Cor. Common to Sec. 23,24,25 & 26 - Fd. 1/2" x 18" Rebar in Bit. Rd.- 61.87' West of found bent 5/8" rod in Mon. Box in intersection of Old State & Maple Grove Rds. 1/2" Rebar accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K9 - Replace 1/2" x 18" Rebar w/ 2" Alum. Cap on 5/8" x 34" Rebar in Mon. Box
 S27°E 27.24' to nail and tag in SW side of Power Pole
 N45°W 97.01' to nail and tag in S side of 10" Ash
 S68°E 104.78' to nail and tag in S side of Power Pole (PBL)
 N81°E 111.28' to nail and tag in N side of Power Pole (PBL)
 East 61.87' to 5/8" Rod in Mon. Box
 S12°W 95.06' to NE Cor. HSE #10026



Signed by Craig W. McVean
 Surveyor's Michigan License No. 39088

Date 10/18/2000